



US Perspective on LC and Update on X-Band LC

Nan Phinney

La Thuile Rencontres de Physique
March 3, 2004



Global Perspective on LC



(Prof. Sugawara Jan 03)



US LC Technology Comparison Study

ALCPG defined physics requirements

500 GeV upgradeable to ≥ 1 TeV, 500 fb⁻¹ in 4 years

2 IRs, energy flexibility between $\sqrt{s} = 90$ -500 GeV

crossing angle to allow downstream E, P, Lum diagnostics

(future) possibility of $\gamma\gamma$, e^-e^- , e^+ polarization

Charge:

develop designs for an X-band and SC LC, sited in US

using common cost, schedule, and risk estimation methods

starting from GLC/NLC and TESLA

but modified to meet ALCPG goals

compare luminosity, energy reach, availability, sites, cost & risk

Task Force included both US warm and cold advocates

BNL, Cornell, FNAL, LBNL, SLAC, TJNAF



Task force membership

1. Accelerator physics and technology design task force
 - Chris Adolphsen (SLAC)
 - Gerry Dugan^{1,2} (Cornell)
 - Helen Edwards (Fermilab)
 - Mike Harrison² (BNL)
 - Hasan Padamsee² (Cornell)
 - Tor Raubenheimer² (SLAC)
2. Site-specific civil design (CA and Fermilab sites) task force
 - Dave Burke² (SLAC)
 - Clay Corvin (SLAC)
 - Dave Finley² (Fermilab)
 - Steve Holmes^{1,2} (Fermilab)
 - Vic Kuchler (Fermilab)
 - Marc Ross (SLAC)
3. Cost and schedule task force
 - Dave Burke^{1,2} (SLAC)
 - John Cornuelle (SLAC)
 - Dave Finley² (Fermilab)
 - Warren Funk (Jefferson Lab)
 - Peter Garbincius (Fermilab)
 - Mike Harrison² (BNL)
 - Steve Holmes² (Fermilab)
 - Ted Lavine (SLAC)
 - Cindy Lowe (SLAC)
 - Tom Markiewicz (SLAC)
 - Hasan Padamsee² (Cornell)
 - Brett Parker (BNL)
 - Kem Robinson (LBNL)
 - John Sheppard (SLAC)
4. Availability Design and Specification
 - Paul Czarapata (Fermilab)
 - Helen Edwards (Fermilab)
 - Tom Himel¹ (SLAC)
 - Marcus Huening (Fermilab)
 - Nan Phinney (SLAC)
 - Marc Ross (SLAC)

¹Primary liaison to USLCSG Accelerator Subcommittee

²USLCSG Accelerator Subcommittee member

DESY points-of-contact:

Cost/schedule and siting: Franz Peters

Design: Stefan Choroba



US Reference Designs

Basic approach:

define a US SC or NC machine we would be willing to build
applying similar levels of conservatism for both

SC design:

upgradeable to 1 TeV, higher initial gradient to reduce cost
more & improved diagnostics, additional overheads and margins
longer e^+ source > 150 GeV for E range, better stability, yield
two tunnels for reliability, 2 IRs, X-angle, etc.

NC design:

add undulator e^+ source to allow polarized e^+ upgrade

Report should be released very soon



Conclusions from US Study

General:

Both options are at comparable levels of development
Both can reach ~ 625 GeV energy with reduced luminosity

Cold option has $\sim 25\%$ higher design luminosity
Cold option is $\sim 42\%$ longer (47 km)

Both options can upgrade to 1 TeV without additional tunnels.

Warm can reach ~ 1.3 TeV

Cold has $\sim 25\%$ higher design luminosity, but cannot reach > 1 TeV

Cost & Schedule:

$> 2/3$ of costs are technology independent, equal for cold & warm

Costs specific to cold are twice those specific to warm

Given adequate funding, both can be built on same schedule,
but commissioning takes longer for cold because of shared tunnels



Conclusions from US Study (2)

Availability:

Based on MC simulation of failures, repairs, access, recovery, MD
Both options can have comparable availability for 2-3% extra cost
An undulator-based e^+ source has a major impact on operability
could reduce delivered luminosity by 20% for stable operation,
and by > 50% during first few years
Single tunnel has lower uptime, improvem't costs ~ balance savings

Risk Assessment:

Based on highest level parameters - energy, luminosity, availability
Risks are comparable for both designs
greatest risks in BDS, MPS, controls - not in RF systems
cold has higher risk in DRs - inherent with pulse structure
warm has higher risk in main linac rf and emittance control



X-Band R&D Status



Why X-band is the right choice?

The technology is demonstrated

TRC R1s and R2s for RF have been met (or due soon)

It is a complete project - all systems are prototyped

test facilities verify the designs for subsystems

ATF, ASSET, E-158, FFTB, GLCTA, NLCTA + more

SLC verified the integrated system

There is a strong US-Japan collaboration

most of the team that will build the LC have expertise in X-band

It is the path to higher energies


1.3 TeV in phase II and a stepping stone to multi-TeV

CLIC only viable option - chance to learn necessary techniques

upstream systems ~ identical to CLIC, could be reused



NLC Collaboration



Fermilab




UC Davis
Ohio State

Los Alamos
Stanford



Nagoya




British Columbia




Queen Mary
Brunel



BINP







GLC Collaboration



Japan (63)




S. Korea (13)



China (10)



India (7)



Taiwan (7)

121 Institutions
on author list
for JLC Roadmap




Australia (2)



Philippines (2)




Vietnam (2)



Singapore (1)




Thailand (1)



USA (6)




Germany (2)



Russia (2)



UK (2)





France (1)



GLC/NLC Accelerator Design Basis

SLC and FEL's


SLC, FFTB, ASSET,
Col. Wake, E-158



SLC, E158,
Nagoya Univ.




ATF, 3rd gen. SRS, SLC DR's




Bunch Comp.

ϵ preservation

e^+ / e^- sources





SLC and FFTB




BDS & IR

KEK and SLAC
X-band RF





SLED-II Demonstration (TRC R1-2)





SLED-II Demonstration (TRC R1-2)

Full power test in NLC Test Accelerator - Jan 2004

Rapid turn on


Easy commissioning &
robust operation

Achieved ~600 MW

> 20% higher than design


Now operated 24/7

> 500 hours stable
operation with
pulse-flattening
feedback






X-Band test Structures





Structure High Gradient Performance

(Breakdown Rate -vs- Unloaded Gradient)





GLC/NLC RF Sub-unit Tests (TRC R2-2)

Goal is to demonstrate a full rf power unit in 2004


2-pack modulator, 2 PPM klystrons, SLED-II, 8 60-cm structures

Rf power unit is replicated ~1000 times in each linac

Two phases: Phase 2a in Spring 2004, Phase 2b in the Fall 2004

From SLED

Staged approach maximizes testing of PPM
klystrons and other structures in parallel





TRC R&D Rankings

Ranking 1

R&D needed for feasibility demonstration of the machine

Ranking 2

R&D needed to finalize design choices and ensure reliability of the machine

Ranking 3

R&D needed before starting production of systems and components

Ranking 4

R&D desirable for technical or cost optimization



TRC Rankings Score Sheet

	TESLA	JLC-C	JLC-X/NLC	CLIC	Common
R1	1	1	2	3	0
R2	6	2	2	6	9
R3	17	2	15	>7	26
R4	5	1	5	N/A	7



TRC Score Sheet (Details)

R1-1	Gradient	Mostly Done	Completed 5~6 of the 13 TRC R1 and R2 items identified for the X-band design with expectations of completing 4 to 5 more in 2004
R1-2	SLED-II	Done	
R2-1	Klystron	Done	
R2-2	RF Unit	Completion expected in 2004	
R2-3	E-cloud	Active program with demonstration planned in 2006	
R2-4	Ions	Active program with benchmarks planned in 2004	
R2-5	DR kicker	Done	
R2-6	DR ε	Done - ATF & ALS results better than simulation!	
R2-7	LET tuning	Active program with results expected in 2004	
R2-8	Instrumentation	Active program with many elements done	
R2-9	Linac Vibration	Active program with demonstration in 2005	
R2-10	Availability	Done - 1 st pass with important conclusions	
R2-11	LET tuning	Active program with results expected in 2004	



Personal Conclusions

For the health of international HEP,
the LC should be located in the US or Japan

The US should bid to host the LC

The US will participate with any location or technology

X-band is the best choice

The technology is demonstrated

Design is complete & lower risk - all systems prototyped

There is a strong experienced team to build it

It is the path to higher energies, > 1 to multi-TeV
and it is less expensive